

EMMET COUNTY REMONUMENTATION PROGRAM
CORNER NO. 127

34-6-M5 = 34-5-A5
T34N R6W 7/12/13/18
CEMETERY ROAD

Date	Surveyor	Found	Witnesses	Notes
1840	GLO	Set post	S31E 25L 14" beech N22W 43L 10" beech	
1881	Keep	ran S/L Sec. 7, appears to have fd. cor.		
1885	Keep	ran S/L Sec. 7, appears to have fd. cor.		
1894	Main	fd. stone,	1) N37E 59L 4" maple 2) S86E 28.5L 4" maple	
1903	Palmer	fd stone with "x" on top.		
1961	Bold	set "T-iron", survey for consumers power.	3) NNE 99.55' 8" maple 4) E 33.00' "T-iron" 5) SW 29.15' nail/washer twin elm	
1963	G. Young	Fd "T-iron", survey for Spears (487).		
1965	G. Young	Fd "T-iron", survey for Seiler (567).		
1970	MDOT	Fd 3/4" iron bar set mon. box.	6) S85E 36.67' 7) S50E 26.00' 8) S50W 74.18'	fence post pp ne cor. hse fnd.
1977	Green	Fd 3/4" iron rod, survey for Kauffman.	9) NE 86.46' 4) E 32.85'	pp "T-iron"
1977	G. Young	Fd 3/4" iron in mon. box, surveys for (Ruzinsky(1280), and Eppler(1286).	7) S53E 26.00' 10) S78W 31.75'	pp 4" pine
1983	J. Young	Fd. 3/4" iron bar, survey for Gokee. as witnessed by MDOT.		
1985	Green	Fd 1" iron rod, survey for Rasmussen.	7) S46E 25.98' 11) S37W 66.75' 10) S83W 31.90'	pp 8" birch 6" pine
1986	Trowbridge	LCRC (L2-161), fd 3/4" iron bar in mon. box.	9) N31E 86.40' 7) S47E 25.98' 10) S82W 31.56'	pp pp 8" pine
1994	Oelke	Fd 3/4" iron rod, survey for R.G. Properties.		
1995	Chamberlain	Fd 3/4" iron rod, survey for Germond. as witnessed in (L2-161)		
1995	Swenor	Fd 1" rod, surveys for Brecheisen(L561-827). as witnessed in (L2-161)		