

MAY 05 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

96 DEC 31 PM 2:25

Glenn R. Sipe
REGISTER OF DEEDS

LIBER A
PAGE 129

Register of Deeds Stamp & File Number

For corners in Emmet Located In: Littlefield Township Corner Code #
(County)

1. Public Land Survey	T <u>35N</u> R <u>4W</u>	<u>C-4</u>
ECRP #40	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Trowbridge, in a field survey on December 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4..... Corner common to Sections 7 & 8, T35N, R4W

See Emmet County Remonumentation Program chronology of GLO corner on back side of this page.

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. Oelle
12-30-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4..... Corner common to Sections 7 & 8, T35N, R4W

Found T-iron, cap no. 15401

Found Witnesses

- 5) S86°E 4.88' 7" Maple (spike in north face)
- 8) N52°W 24.65' 10" Beech (spike in south face)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4..... Corner common to Sections 7 & 8, T35N, R4W

The T-iron was removed and replaced with a 2" diameter x 30" long PVC pipe, a base magnet and a standard brass Emmet County Remonumentation cap. This position is accepted as a careful and faithful perpetuation of the original corner.

New Witnesses

- 8) N52°W 24.65' 10" Beech (spike in south face) added 27463 cap below found spike
- 9) Az.112° 41.89' 6" Beech (27463 cap in south face)
- 10) Az.257° 30.79' Twin Beech (27463 cap in south face)
- 11) Az.181° 44.43' 5" Maple (27463 cap in east face)

Signed by Michael A. Trowbridge Date December 19, 1996
Surveyor's Michigan License No. 27463

EMMET COUNTY REMONUMENTATION PROGRAM

LIBER A

CHRONOLOGY OF GLO CORNER

PAGE 130

REMON. CORNER # 40 LCRC # 35-04-C4 TOWNSHIP...LITTLEFIELD

CORNER COMMON TO SECTIONS 7 & 8, T35N, R4W

DATE	SURVEYOR	FOUND/POST	WITNESSES:
1840	GLO	Set Post	1) S58°E 18 Lks 10" Beech 2) S68°W 55 Lks 14" Beech
1888	Keep	Appears to have found corner. Set center 1/4 corner of sec. 7.	
1888	Keep	Appears to have found corner. Ran E & W 1/4 line of sec. 8.	
	ECRC	Set standard Emmet County marker.	3) S87°E 2.08' 8" Maple 4) N53°W 27.33' 7" Beech
1970	Green	Survey for MBT shows found standard Emmet County marker.	
	ECRC	Set "T-iron" at prorated position.	
1978	Green	Survey for Kirkley (305/783) found "T-iron".	
1979	Green	Survey for Holmes (305/754) & (305/755) found "T-iron".	
1980	Green	LCRC 2/36, found "T-iron".	5) S86°E 4.88' 7" Maple 6) S32°E 12.82' twin Maple 7) N55°W 24.64' 8" Birch
1980	Green	Survey for McIssac (316/282) found "T-iron".	
1981	Green	Survey for Armock (316/306) found "T-iron".	
1983	Green	Survey for Holmes, found "T-iron".	
1990	Trowbridge	Survey for Welsh, found T-iron.	8) N52°W 24.65' 10" Beech