

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

Located In	Corner Code #
T 35N R 4W	A-5
T 35N R 4W	B-5
S T R	
S T R	
S T R	
S T R	

Recorded Plat: \_\_\_\_\_

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	•											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

B-5 G.L.O. John Mullett D.S. 1840  
 Wit: Hemlock 8" N49°W 20 links  
 Beech 6" S54°W 20 links

B-5 G.L.O. John Mullett D.S. 1840  
 Set quarter section post  
 Wit: Beech 10 S71°W 34  
 Beech 10 S28°W 95

R. Oelke P.S. #33983, Liber 3, Page 32  
 Found "T" iron for corner  
 Wit: Maple 12" S75°E 38.80'  
 Ash 5" S60°W 102.64'  
 P. pole N40°E 88.74'  
 Aspen 16" N40°W 35.16'

R. Oelke P.S. #33983, Liber 3, page 32  
 Found 1-1/2" iron pipe at road intersection  
 Wit: P. Pole S25°E 64.34'  
 P. Pole S40°E 65.61'  
 40" Maple S20°W 43.55'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:  
 A-5 Found and accepted a "T" iron as witnessed by R. Oelke P.S.

B-5 Found and accepted a "T" iron fitting R. Oelke P.S. Witnessed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 "T" iron  
 Wit: 6" Maple N26°W 51.47'  
 10" White pine S73°W 91.38'  
 9" Hemlock S21°E 50.21'  
 \*16" Poplar N33°W 35.14'  
 \* Power Pole N43°E 88.74'  
 Centerline of blacktop road South 1.5'

B-5 "T" iron  
 Wit: 4" Cherry N76°E 94.32'  
 \*Power Pole S55°E 65.62'  
 Power Pole S24°E 64.35'  
 Fence corner post S53°W 45.22'  
 Centerline of E-W road North 2'

\*Old witnesses by R. Oelke P.S.

\*Old witnesses by R. Oelke P.S.

Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 9-29-99

