

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

Corners In:	Located In	Corner Code #
Public Land Survey	T <u>35N</u> T <u>35N</u>	R <u>4W</u> R <u>4W</u>
Property Controlling Section	S _____ S _____	R _____ R _____
Miscellaneous Property in Section	S _____ S _____	R _____ R _____
Recorded Plat: _____		
Lot No: _____		
Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1	●												
2		6		5		4		3		2		1	
3													
4	●	7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Carl T. Kiiskila, in a field survey on May 6, 1998 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-1 GLO William Burt, 1840, set post  
Wit: Beech 16" N65°E 36 links  
Beech 10" S67°W 22 links

James Green RLS #1540,1 Liber 1, page 210, shows found Emmet County marker for corner, May 24, 1976.

Thomas Swenor LLS #37282, Liber 485, Page 875, found 1/2" re-rod for corner, December 1992.

A-4 GLO John Mullett 1840, set quarter section post  
Wit: Beech 10" S55°E 28 links  
Beech 10" S70°W 8 links

Nicholas B. DeYoung, RLS #20705, August 17, 1977, certificate of survey shows 1/2" rod.  
Wit: 10" Maple West 1.0'  
6" Beech N75°W 14.8'

James Green RLS#15401, Liber 316, Page 282, found 1/2" rod for corner.  
Wit: 10" Maple West 1.0'  
6" Beech N75°W 14.8'

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

A-1 Found a 1" Iron pipe fitting James Green RLS and Thomas Swenor PS witnesses.

A-4 Found 1/2" iron bar fitting Nichlas B. DeYoung RLS and James Green RLS witnesses.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-1 Raised 1" iron pipe with 5/8" X12" rerod with PS cap and added monument box.  
Wit: 5" Red Pine S45°W 83.34'  
\*22" Maple N80°E 86.80'  
5" Cherry S21°E 105.94'  
Power Pole N45°W 112.21'

A-4 Set 1"x32" iron pipe with PS cap and carsonite post  
Wit: \*14" Poplar S49°E 16.15'  
\*8" Beech N84°E 14.61'  
8" Beech N25°W 27.32'  
\*12" Triple Maple N65°W 1.37'  
Centerline of trail (Bears N37E) North 13.5

\* Old witnesses by James Green and Thomas Swenor

\*Old witnesses by others

Signed by: Carl T. Kiiskila  
Surveyor's Michigan License No.: 33981

Date: 9-29-99

