

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:	Located In	Corner Code #
Emmet (County)		
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>35N</u> R <u>4W</u>	<u>5</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6												
3													
4	7												
5													
6	18												
7													
8	19												
9													
10	30												
11													
12	31												
13													

I, Carl T. Kiiskila, in a field survey on May 6, 1998 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

5- This corner was not established during the original government survey.

6- This corner was not established during the original government survey.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

5- Established the southwest corner of the northwest quarter of the northeast quarter of section 6 per standard BLM instructions for the subdivision of a section.

6- Established the southeast corner of the northwest quarter of the northeast quarter of section 6 per standard BLM instructions for the subdivision of a section.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 - Set 5/8" x 32" rerod with PS cap and carsonite post.
 Wit: 16" Beech S 48° W 15.16'
 5" Beech S 23° E 16.35'
 5" Beech N 77° E 11.48'
 14" Maple N 29° W 24.75'

6- Set 5/8" X 32" rerod with PS cap and carsonite post.
 Wit: 6" Maple N01°W 46.10'
 9" Scotch Pine N67°E 17.92'
 8" Scotch Pine S27°E 11.30'
 8" Scotch Pine S47°W 5.65'
 Centerline of east-west road south 115'

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 9-29-99



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 Revised May 14, 1975
 Revised Jan. 1983
 Revised Oct. 1995

Surveyor's Michigan License No. 33981



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 Revised May 14, 1975
 Revised Jan. 1983
 Revised Oct. 1995