

**SURVEY &
REMONUMENTATION**

MAR 13 2000

SECTION

LIBER A
PAGE 320

**EMMET COUNTY REMONUMENTATION PROGRAM
CORNER NO. 212**

35-5-G-7

T35N R5W section corner bet. Sections 15,16,21, & 22
menonaqua swamp

Date	Surveyor	Found	Witnesses	Notes
1840	GLO	set post	1) N 19°E 19L 7" Cedar 2) S 71°W 17L 15" Cedar	
1903	County	shows distances to corner		
1914	Keep	shows corner on Plat of Me-non-a-qua Beach		
1941	Lee	6" square wood post, Replaced with conc. Mon		
1960	Miller	L.C.R.C., found concrete monument	1) found stump 2) found as wind fall	
Notes on Millers LCRC.				
1929	Robinson (Irish says this was Lee) reports cedar stake which he replaced with a concrete monument Wilcoxon reports bearing tree standing (1940 +/-)			
Miller capped monument with standard Emmet county Cap and propped up (2) GLO				
New witnesses				
3) N 49°E 16.5' 6" Birch				
4) N 59°W 79.5' 13" Cedar				
Miller has some doubts about corner relative to bearing tree evidence. See notes.				
1961	Irish	Found conc. mon.		
1969	Bidstrup	corner is labeled "monument set by Ted Miller in 1960. Original S.W. corner of sec.15 (obliterated) was 3' +/- south of new corner."		
1978	Green	shows symbol		
1982	Young	found Emmet County marker on concrete monument		
5) S 81°E , 9.92', 24" W. pine				
6) S 28°W , 23.80', 18" Cedar				
7) N 22°W, 20.94', 9" Y. birch				
1998	Oelke	LCRC Liber 3, page 190, found concrete monument, added new witnesses		
8) N 19°E , 19.48, 12" Birch, tagged 33938 in E face				
9) N 79°E , 23.27', 14" Birch, tagged 33983 in S face				
10) S20°W, 24.00', 24" Cedar, tagged 33983 in E face				
11) N30°W, 21.08', 12" Birch, tagged 33983 in W face				