

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


EMMET COUNTY  
T 35 N R 5 W

DESCRIPTION OF CORNER S 1/16 corner on N-S 1/4 line, or SE cor. of Govt Lot 6, Sec. 27

CORNER MONUMENT Set 1"x36" Pipe

DATE MONUMENT PLACED AND WITNESSED 11-17-70

WITNESSES TO CORNER..... 16" Pine, W. S 61 E Face of tree No Blaze 66.0'



6" Pine, W S 29 W Face of tree No Blaze 58.8'

Centerline R.R. Track N 38 W 42.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a boundary survey in this area. The corner was established equidistant and on line between found 1/4 corner to the South and Center of Section to the North. The center of Sec. to the North is a point 5.6' West of old square concrete monument by Lee in 1942. By using a center of Section 5.6' West of Lee's square concrete monument, we agree with the 1/4 line for 1/2 mile North as surveyed and monumented by G. E. Young and T.R. Miller.

The Latitude of our 1/16 corner would agree with a 1/16 corner as dimensioned on Lee's drawing of the Tannery survey. Lee's drawing does not indicate that he set a physical corner at this point.

Also see Land Corner Record for Center of Section 27.

SURVEYOR'S SEAL

SIGNED

*Carl F. Boer*  
REGISTERED LAND SURVEYOR 12028

DATE

11-24-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68