


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

LMHET COUNTY  
T 35 N R 5 W

DESCRIPTION OF CORNER W 1/16 Corner common to Sections 27-34, or SE corner of  
Govt Lot 7, Sec. 27  
CORNER MONUMENT Found 4" square conc. monument. Left in place.  
DATE MONUMENT PLACED AND WITNESSED 11-17-70

WITNESSES TO CORNER.....



5" Cedar N 57 E 31.0'  
7" Maple N 14 W 15.8'  
AND In edge of small lake

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a boundary survey in this area. The corner was recovered by R. G. Lee in Tannery survey in 1942. He placed the square monument. The monument is on line between found Section corner to West and found 1/4 corner to East and within less than 2.5' of being equidistant between the 1/4 corner and Section corner. We therefore have accepted Lee's square concrete monument as the proper SE corner of Govt. Lot 7, Sec. 27.

Richard Bidstrup, RLS & P.E. Harbor Springs, has also used this corner for surveys in Section 34.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Carl F. Roover*  
REGISTERED LAND SURVEYOR 12028

DATE

11-24-70

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing