

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


EMMLT COUNTY  
T 35 N R 5 W

DESCRIPTION OF CORNER (1/16 corner) Center of SW 1/4 Sec. 27; or NE corner of Govt. Lot 7, Sec. 27.

CORNER MONUMENT Set Dept. Concrete Mon with Alum. Cap

DATE MONUMENT PLACED AND WITNESSED 11-17-70

WITNESSES TO CORNER..... 4" Sq. concrete Mon. N 65 E 37.3'



3" W Pine N 78 E 36.4'

4" R. Pine S 35 E 56.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a boundary survey in this area. We could not accept R. G. Lee's square concrete monument as placed during Tannery survey in 1942 because he placed his monument 70' from where his dimensioned drawing says he placed it. A review of his Tannery survey drawing will show that when he subdivided the West 1/2 of Sec. 27 he made very definite errors. Our position for the NE corner of Govt. Lot 7, Sec. 27 is based on complete controlling corners for Sec. 27 and the standard directions for subdivision of sections by the Federal Bureau of Land Management.

Also refer to our Survey Map.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roover*

12028 DATE

11-24-70

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68