


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

EMMET COUNTY
T 35 N R 5 W

DESCRIPTION OF CORNER Center of Section 27
CORNER MONUMENT Set Dept. Concrete Monument with Alum. Cap.
DATE MONUMENT PLACED AND WITNESSED 11-17-70
WITNESSES TO CORNER.....



10" Maple	S 39 E	46.9'
9" Maple	S 25 W	65.2'
AND Old 4" Sq. conc. mon.	LAST	5.6'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a boundary survey in this area. The position for the center of section is the same as established in a complete survey of the N-S 1/4 line by T. R. Miller, RLS, as recorded at the Emmet County Register of Deeds Office on August 7, 1962. The departure of this center of section in essence would be on a straight line 1/4 line between the North and South 1/4 corners of Sec. 27. The latitude was positioned at a point 5.6' West of old square concrete monument by Lee.

Miller's survey gives a history of Lee's square concrete monument and shows why he accepted a position for the center of Sec. 27, 5.6' West of Lee's monument. By accepting Miller's survey we have used a center of Section and true N-S 1/4 line, which has a minimum of adverse effect on adjoining land owners. Miller's survey is monumented and has been used by RLS G.E. Young.

SURVEYOR'S SEAL

SIGNED

Carl F. Basler

DATE

11-24-70

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68