

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 36 N. R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner on north side Section 5

CORNER MONUMENT Set 1" x 24" pipe

DATE MONUMENT PLACED AND WITNESSED June 25, 1962

WITNESSES TO CORNER.....



18" Elm S 56 E 38.8'

12" H. Maple S 37 W 56.1'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was found while making a survey in this area. Found a 4" x 4" piece of strap iron (sleigh runner), also part of old coal shovel and a railroad spike at corner, which we conclude to be 1/4 corner for Section 5 since it falls midpoint between closing section corners and only 5 links out of line. Also falls nearly in line with 1/4 line road running south. Probably established at the same time as the Section corners of Section 5 which were recovered.

1/4 corner for Section 32, T 37 N, R 5 W is 10 links east.

**SURVEYOR'S SEAL**

SIGNED *Kenneth J. Oetting* DATE July 16, 1962  
REGISTERED LAND SURVEYOR