

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 36 N.R. 5 W.
T. 37 N.R. 5 W. Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3 - 4 - 33 - 34

CORNER MONUMENT Set 1" pipe with 4" brass cap below surface

DATE MONUMENT PLACED AND WITNESSED June 19, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" Cedar N 70 W 50.1'
6" Cedar N 46 E 25.0'
AND
4" Cedar S 3 E 35.2'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between standard corners 1 mile east and 1 mile west. Unable to locate anything for a previous corner, but this position is supported by old blazes running north between 33 - 34. Falls about 10' north of apparent centerline of E - W county road.

Closing corner to Sections 2 - 3, T 36 N, R 5 W is 10 links west.

SURVEYOR'S SEAL

SIGNED *Francis J. Oetting* DATE June 21, 1962
REGISTERED LAND SURVEYOR