

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner on north side Section 4

CORNER MONUMENT Drove 1" x 24" pipe

DATE MONUMENT PLACED AND WITNESSED June 19, 1962

WITNESSES TO CORNER.....



10" Balsam S 33 E 41.0'

7" Cedar S 23 W 41.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners while making a survey in this area. Falls about 12' north of centerline of E - W county road.

1/4 corner for Section 33 is 4 links east.

SURVEYOR'S SEAL

SIGNED Kenneth J. Oetting DATE June 21, 1962
REGISTERED LAND SURVEYOR