

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 36 N.R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 5 - 6 on north boundary of township

CORNER MONUMENT Set 1" pipe with 4" aluminum cap below surface of road

DATE MONUMENT PLACED AND WITNESSED June 25, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

Fence corner South 29.3'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this area. Found pile of various colored rocks at corner below surface of E - W county road. Falls in line with old fence south and is properly located with reference to standard corner to Sections 31 - 32. Probably perpetuated in early local survey.

Corner to Sections 31 - 32, T 37 N, R 5 W is 12 links east.

SURVEYOR'S SEAL

SIGNED

*Kenneth Postling*  
REGISTERED LAND SURVEYOR

DATE June 27, 1962