

SECTION

LAND CORNER RECORDATION CERTIFICATE 98 DEC 30 PM 12:00
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

EMMET
(County)

Located In:

Corner Code #

Glenna D. Sizer
REGISTER OF DEEDS

- 1. Public Land Survey T 36N R 4W A9
ECRP #189 A
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

Volume A
PAGE 146

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Michael A. Trowbridge, in a field survey on October 21, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M9, CORNER COMMON TO SECTIONS 19, & 30, T36N, R4W
SEE CHRONOLOGY ON BACK OF THIS FORM FOR CORNER HISTORY.

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. DELKE, P.S. EC. REP.
29 DEC. 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M9, CORNER COMMON TO SECTIONS 19, & 30, T36N, R4W

Dit not find 1840 GLO post or witnesses. Did not find Hartzler's stone of 1879 (dug 2' diameter by 3' deep hole).

Found 5/8" rerod in monument box set in 1978 by Richard Bidstrup at intersection of roads north, south, east and west.

Found witnesses

- 7) S66°E (Az.114°) 82.92' 6" Poplar
- 8) S46°E (Az.134°) 68.97' 6" Poplar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M9, CORNER COMMON TO SECTIONS 19, & 30, T36N, R4W

The 5/8" Rerod noted above was removed, and replaced with a 2" diameter, 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap, which was placed within a standard Emmet County monument box. This position is accepted as the best available evidence of the position of the original corner.

ADDITIONAL NEW WITNESSES:

- S63°E (Az.117°) 83.01' 10" Poplar (27463 cap & nail in North face, set above found witness 7)
- S54°E (Az.126°) 69.01' 10" Poplar (27463 cap & nail in East face, set above found witness 8)
- S46°E (Az.134°) 60.10' Wolm. 4x4 Phone Ped. Post (27463 cap & nail in NE corner)
- S13°E (Az.167°) 94.65' Power Pole (27463 cap & nail in West face)



Signed by Michael A. Trowbridge
Surveyor's Michigan License No. 27463

Date 12-8-98

APR 29 1993

SECTION

LIDER A

PAGE 147

EMMET COUNTY REMONUMENTATION PROGRAM

CHRONOLOGY OF GLO CORNER

REMON. CORNER # 189 LCRC # 36-04-A9 TOWNSHIP...MAPLE RIVER

CORNER COMMON TO SECTIONS 19/30, T36N, R4W

DATE	SURVEYOR	FOUND/SET	WITNESSES		
1840	GLO	Set Post	1) S42°E	32 lks.	10" Beech
			2) N10°W	30 lks.	12" Beech
1879	L. Hartzler County Surveyor Pleasantview Twp. Highway Records Pgs. 74-77	Stone	No Witnesses		
1978	R. E. Bidstrup Survey Map L. 285, Pg. 829	Set 5/8" Rerod	3) S40°E	65.83'	16" Aspen
			4) N40°W	47.56'	Fence Post
			5) East	50.04'	Spike
1990	M. Trowbridge Survey Map	Found 1/2" Rerod	6) S36°E (az. 144°)	43.87'	4" Tele. Post
			7) S66°E (az. 114°)	82.92'	6" Poplar
			8) S46°E (az. 134°)	68.97'	6" Poplar
			9) N22°W (az. 338°)	51.6'	Stop Sign
1990	M. Trowbridge LCRC L. 2, Pg. 315	Found 1/2" Rerod (Record of 1990 Rerod)	6) S36°E (az. 144°)	43.87'	4" Tele. Post
			7) S66°E (az. 114°)	82.92'	6" Poplar
			8) S46°E (az. 134°)	68.97'	6" Poplar
			9) N22°W (az. 338°)	51.6'	Stop Sign
1992	J. E. Young Survey Map L. 506, Pg. 581	Found 5/8" Rerod	3) S40°E	65.83'	16" Aspen
			4) N40°W	47.56'	Fence Post
			5) N90°E	50.04'	Spike

