

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION

For corners in

EMMET
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

1994 DEC 28 AM 11:04

	Located In:	Corner Code #
	MAPLE RIVER	
1. Public Land Survey	T <u>36N</u> R <u>4W</u>	<u>B-11</u>
ECRP #58	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Alexandra C. Sijan

REGISTER OF DEEDS

LIBER A

PAGE 67

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Richard E. Oelke 20 December, 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

B-11, 1/4 corner between sections 30 & 31, T36N, R4W

(SEE BACK OF PAGE FOR HISTORY)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11, 1/4 corner between sections 30 & 31, T36N, R4W

Found 2" iron pipe, 2.5' long, 1.5' below the surface of gravel road. I excavated around pipe and found no other evidence.

- (4) N18°W, 29.8', 14" elm stump
- (6) S00°E, 33.08', "T-iron"
- (9) N20°W, 28.20', 4" maple, spike in W face
- (10) N00°E, 32.97', "T-iron" capped #15402
- (11) N30°E, 60.96', 10" cheery, nail W face
- (12) S32°E, 67.59', 10" cherry, tagged #33983 in NE face
- (13) S45°W, 109.96', 18" spruce, 40d in SE face
- (14) N43°W, 50.34', 8" maple, nail in NE face

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. OELKE
27 Dec. 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-117, 1/4 corner between sections 30 & 31, T36N, R4W

At the 2" iron pipe, set a 2" diam., 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap, 12" below the surface. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

No additional new accessories were taken



Signed by Richard E. Oelke Date 20 DECEMBER 1994
Surveyor's Michigan License No. 33983

EMMET COUNTY REMONUMENTATION PROGRAM
CORNER NO. 58

36-4-B11
T36N R4W 1/4 30/31
Valley Road

LIBER A
PAGE 68

ate	Surveyor	Found	Witnesses	Notes
1840	GLO	Set post	N27°E, 281ks, 12" sugar; S27°E, 121ks, 8" beech	
1972	Green	Survey for Barch, found 2" iron pipe.	(1) S27°E, 68.20', 5" maple (2) S20°W, 33.90', 15" hemlock	
1975	Bidstrup	Survey for Kuhnhen, found 2" iron pipe.	(3) S20°W, 33.9', 5" maple (4) N18°W, 29.8', 14" elm	
1976	Bidstrup	Survey for Wood, found 2" iron pipe.	(5) S80°E, 23.15', 10" cherry (6) S00°E, 33.00', T-iron (7) N85°W, 16.85', 10" cherry	
1987	Trowbridge	Survey for Croff, found 2" iron pipe.	(8) N22°E, 27.31', 7" cherry spike W face (6) S00°E, 33.00', "T-iron" (9) N13°W, 28.23', 4" maple spike W face	
1989	Green	Survey for Donfor, found 2" iron pipe and witness (8) & (9).	(10) N00°E, 33.01', 1/2" iron rod	
1992	Oelke	Survey for Weirtalla, found 2" iron pipe. marker.	(11) N30°E, 60.96', 10" cherry tagged W face (12) S32°E, 67.62', 10" cherry tag 33983 E face (6) S00°E, 33.05', T-iron #15401 (13) S50°W, 110.10', 12" cherry 40d in SE face (14) N43°W, 50.35', 8" maple nail in NE face	