



EMMET COUNTY REMONUMENTATION PROGRAM  
**CORNER NO. 131**  
 T36N R4W - F-1(cc)

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

Date	Surveyor	Found	(Witnesses)	
1840	GLO	North 1/4 Corner Section 4, not set on correction line. Missing corner is set midway between closing corners east and west.		
Circa 1960	E.C.R.C.	1/4 corner on north line of section 34, T36N R4W . 1/4 corner on South line of Sec. 33, T37N R4W is 8.63 feet East.	(1) (2) (3)	N37°E 56.50' - 4" Jack Pine S45°W 90.95' - 6" Red Pine S20°E 95.30' - 6" Red Pine
1970	Schweigert and Young	Notes distance from Center 1/4 Corner to North line Sec. 4		No witnesses.
1984	M.A.Trowbridge	Wrong Corner		
1984	M.A.Trowbridge	Set 1/2" re-rod, after meeting with Robert Mitchell- Kingsley	(4) (5) (6) (7)	N18°E 60.40' - 4" Jack Pine S45°E 86.05' - 7" Red Pine S52°W 44.66' - N.E. Cor. Tele. Ped. East 8.58' - 1/2" Re-Rod (standard corner) (L.2, P.118, LCRC)
1985	J.B. O'Neill	Notes M.A. Trowbridge Irons		8.66 feet apart
1985	J.E. Young	Notes using South 1/4 Corner Sec. 33, as established by Trowbridge		
1992	M.A.Trowbridge	Found 1/2" re-rod		Same as above
1996	Granger and Assoc.	Work performed in south part of Sec. 4. No mention of subject corner		No witnesses.