

98 DEC 31 AM 10:04

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

EMMET

(County)

Located In:  
MAPLE RIVER

Corner Code #  
TOWNSHIP

1. Public Land Survey

T 36 N R 4 W

K-2

**ECRP# 170**

2. Property Controlling  
in Section

S      T      R       
S      T      R     

3. Miscellaneous  
Property in Sec.

S      T      R       
S      T      R     

*Glenna A. Lipe*

REGISTER OF DEEDS

LIDER A

PAGE 288

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Richard E. Oelke, in a field survey on 11 November, 1998  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as  
required in the current manual of survey instructions of the United States Department of the Interior,  
Bureau of Land Management or by a decree of a Court of Law and /or that the corner points  
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of  
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,  
re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
**K-2..... Corner between section 1 & 2, T36N, R4W**

See Outline of Corner History on back.

GLO in 1840 set post.... Main in 1891, set new post from gov't. bearing trees.... Main in 1894, set new post from gov't. bearing trees.... Emmet County Road Commission 1970's, found iron stake..... G. Young in 1974 found 1" iron pipe.... 1" iron pipe has been used to the present...Note: Doyle set or used another cor. approx. 7' SE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**K-2..... Corner between section 1 & 2, T36N, R4W**

Found iron plow handle 4' long, 1' below grade in road, at PI of road. (this is 1" pipe mentioned above)  
WITNESSED AS FOLLOWS:

S71°W, 61.35'	found root wad,	(rec) S 76°30'W,	60.72',	14" norway pine (D)
S52°W 66.94'	found 8" stump,	(rec) S53°W,	66.60'	6" Poplar (1)
S87°W 39.96'	found 8" stump 40d	(rec) S85°W	40.00'	6" Poplar (2)
S73°W 35.17'	found 8"stump	(rec) S65°W	36.00'	7" Aspen (4)
N90°W 33.11'	concrete monument	(rec) west	33.00'	concrete monument (5)
N68°W 32.20'	8"stump, 10710 tag	(rec) N68°W	31.85'	5" Aspen (6)

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County  
R.E. OELKE, P.S. E.C. Rep  
29 DEC 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**K-2..... Corner between section 1 & 2, T36N, R4W**

The plow handle was replaced with a 2" diameter, 30" long PVC pipe, with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap. This position is accepted as a careful and faithful perpetuation of the original corner.

NEW WITNESSES AS FOLLOWS:

N55°E, 71.69',	6" w. pine tagged 33983	in NW face
S43°E, 71.69',	10" cherry tagged 33983	in NW face
S71°W, 67.30',	6" w. pine tagged 33983	in N face
N47°W, 57.28',	6" w. pine tagged 33983	in NE face
S80°E, 38.48',	concrete monument with U. of M. cap	
S43°E, 7.33',	found 3/4" pipe, 1.7' long,	at surface in yellow stipe of curve

Signed by

R.E. Oelke

Date 11 November 1998

Surveyor's Michigan License No. 33983



MAINTAINED BY  
1797 1855

SECTION 1/4

EMMET COUNTY REMONUMENTATION PROGRAM  
CORNER NO. 170

LIDGR A  
PAGE 289

36-4-K2  
T36N R4W 1/4 CORNER BETWEEN SECTION 1/2  
PLAINS ROAD

Date	Surveyor	Found	Witnesses
1840	GLO	set post	A) S53E 20L 11" Beech B) S28W 30L 10" Beech
1891	Main	set new cedar post with nail from government bearing trees also took new witnesses and set witness posts E&W 0.5 chains	C) N78°45'E 73L 8" Hemlock D) S76°30'W 92L 14" Norway Pine
1894	Main	set new cedar post government bearing trees still stand, again set witness posts E&W 0.5 ch	
1894	Keep	found corner, split Sec. 1	
1970's?	ECRC	found iron stake	1) S53W 66.60' 6" Poplar 2) S85W 40.00' 6" Poplar
1974	G. Young	found 1" pipe in road survey (Wixson)	3) S75E 40.06' fence corner post 4) S65W 36.00' 7" Aspen 5) west 33.00' concrete monument 6) N68W 31.85' 5" Aspen
1975?	Doyle	shows symbol at corner, survey for U of M. It appears that a different cor. than the one above was used or Doyle set a new corner here.	
1995	Trowbridge	found 1" pipe, 1' below grade, survey (Bush)	