

SURVEY &
REMONUMENTATION

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 FEB 14 AM 10:12

For corners in
EMMET COMMISSION
(County)

Located In: Corner Code #

1. Public Land Survey T 36N R 4W M-13
T _____ R _____
T _____ R _____
T _____ R _____
- ECRP #4
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Glenn B. Lipe
REGISTER OF DEEDS

LIBER A
PAGE 1

Register of Deeds Stamp & File Number

I, Thomas D. Swenor, in a field survey on December 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-13
- 1840 G.L.O. Set Post - Cedar 12" N55W 17 links, Cedar 6" S15E 19 links
- 1896 Heyden Partial Sec. Sub'd/County Surveyor Records.
- 1957 Schweigert found wood post & Bearing Tree, and set T-iron (Rec. 1958)
Witnesses - Cedar 8" S61W 12.7', Cedar 8" N86W 60.3'
- 1969 George E. Young - Set Concrete Monument, Witnesses same as above.
- UNKNOWN United Design Associates (Map Only).
- 1991 Jim Granger - Found Concrete Monument - Recorded in Cheboygan County Register of Deeds. Liber 002, Page 143.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-13
- Found as described and recorded in 1991 by Jim Granger. Witnesses fit well, and the history of the corner appears to be consistent with this position. Also found remains of bearing tree as found by Schweigert in 1957. From Concrete Monument to remains of a stump is at N52W 11.60 feet. Also in the Process of placing monument referred to in "C" below a 4" Round post with an axed point, (+/- 6" in Length) was found in the hole that the monument was in. (It appears as though the post was carefully placed along side the Set Concrete Monument, Possibly by G. E. Young).
- This corner is accepted by the Emmet County Remonumentation Group as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-13
- Found and Replaced Concrete Monument with a 2" dia. 30" long PVC pipe with a base magnet and a standard brass Emmet County Remonumentation Cap.
- Found 10" Cedar S2W 11.68' (11.73' Granger Measure) Tag #16041
- Found 10" Cedar N51E 4.55' Tag #16041
- Found 6" Cedar N77E 9.33' Tag #16041
- Set Tag #37282 6" Cedar S70E 14.09'
- Found 6" Cedar S66E 13.94' Tag #16041
- Found Stump Remains Cedar Tree N52W 11.60' No Tag Set...
- carefully placed 4" round by 6" long post in hole of above set monument.

Signed by Thomas D. Swenor
Surveyor's Michigan License No. 37282

Date December 30, 1993

STATE OF MICHIGAN
EMMET COUNTY
SWENOR
No. 37282
LICENSED LAND SURVEYOR
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983