

LAND CORNER RECORDATION CERTIFICATE 98 DEC 30 PM 12:00  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

EMMET  
(County)

Located in:

Corner Code #

*Glenn B. Sizer*  
REGISTER OF DEEDS

- |                                    |                          |           |
|------------------------------------|--------------------------|-----------|
| 1. Public Land Survey              | T <u>36N</u> R <u>6W</u> | <u>19</u> |
|                                    | T _____ R _____          | _____     |
| ECRP #185                          | T _____ R _____          | _____     |
|                                    | T _____ R _____          | _____     |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____     |
|                                    | S _____ T _____ R _____  | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____     |
|                                    | S _____ T _____ R _____  | _____     |

LIBER A  
PAGE 150

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Trowbridge, in a field survey on November 23, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**19, CORNER COMMON TO SECTIONS 22, 23, 26, & 27, T36N, R6W**

SEE CHRONOLOGY ON BACK OF THIS FORM FOR CORNER HISTORY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**19, CORNER COMMON TO SECTIONS 22, 23, 26, & 27, T36N, R6W**

Found 5/8" rod #30095 as noted in chronology on the back of this form.

After removal of the 5/8" rod, no other monumentation material was found (Main's 1913 post, brush hook, and 22 cal. rifle barrel were not found - in a cut area).

Witnesses Found

- 7) S60°E 82.35' Power Pole
- 9) N11°W 41.52' 10" Maple
- 10) N38°E 46.25' 12" Maple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**19, CORNER COMMON TO SECTIONS 22, 23, 26, & 27, T36N, R6W**

The 5/8" rod noted above was removed, and replaced with a 2" diameter, 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap, which was placed within a standard Emmet County monument box. This position is accepted as a careful and faithful perpetuation of the position of the original corner.

ADDITIONAL NEW WITNESSES:

A 27463 cap and nail was set below each of the three above listed Witnesses Found (7, 9, & 10).

S32°W (Az. 212°) 79.65' 7" Maple (27463 cap & nail set in East face)

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County  
R.E. DELKE, P.S. E.C. Rep.  
29 DEC. 1998

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Michael A. Trowbridge

Date 12-8-98

Surveyor's Michigan License No. 27463

**EMMET COUNTY REMONUMENTATION PROGRAM**

**CHRONOLOGY OF GLO CORNER**

REMON. CORNER # 185      LCRC # 36-06-19      TOWNSHIP...FRIENDSHIP

CORNER COMMON TO SECTIONS 22/23/26/27, T36N, R6W

DATE	SURVEYOR	FOUND/SET	WITNESSES		
1840	GLO	Set Post	1) N60°W	22 lks.	12" Beech
			2) S70°E	15 lks.	12" Beech
1913	S. G. Main County Surveyor Record, Pg 39	Found Post Set Brush Hook, Post and piece of 22 cal rifle barrel.	3) N60°E	48'	5" Sugar
1982	R. E. Bidstrup LCRC L. 2, Pg. 94	Set 5/8" Iron bar at intersection of roadways to East, West, & South.	4) S16°E	34.77'	7" Ash
			5) S56°E	38.21'	6-4" Maple clump
			6) N12°E	29.82'	14" Maple
1989	J. B. O'Neill LCRC L. 2, Pg. 262	Found 5/8" bar #30095 2' north of centerline of Wressel Road and at the centerline of 2 track road to the south.	7) S60°E	82.35'	Power Pole
			8) S06°E	68.92'	8" Twin Maple
			9) N11°W	41.52'	10" Maple
			10) N38°E	46.25'	12" Maple
1990	J. B. O'Neill Survey Map L. 450, Pg. 466	Found 5/8" Iron rod	7) S60°E	82.35'	Power Pole
			8) S06°E	68.92'	8" Twin Maple
			9) N11°W	41.52'	10" Maple
			10) N38°E	46.25'	12" Maple

