

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Emmet</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>36 N</u> R <u>6 W</u>	<u>I-3</u>
	T <u>36 N</u> R <u>6 W</u>	<u>J-3</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on Aug 2, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3									●	●			
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-3 GLO John Mullett, D.S. 1840
Set post at corner of Sections 2,3,10, and 11
Wit: 12" Birch S39°E 24 links
8" Birch S58°W 12 links

J-3 GLO John Mullett, D.S. 1840
Set one-quarter section post
Wit: 12" Aspen N58°E 25 links
7" Aspen S24°W 33 links

Liber 1, Page 293, Danny Bongiovanni, RLS #24586
Set 5/8" rered with PS cap
Wit: 8" Poplar S29°W 40.82'
12" Maple S29°E 40.56'
6" Maple South 41.20'

Liber 1, Page 293, Danny Bongiovanni, RLS #24586
Set 5/8" rered with PS cap
Wit: Power Pole N35°W 44.52'
Power Pole S34°W 55.28'
7" Balsam S17°W 52.61'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

I-3 Found 5/8" rered with a battered RLS cap

J-3 Found a 5/8" rered

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 Found 5/8" rered with cap
Wit: 16" Red Pine N45°W 53.81'
*10" Maple South 41.16'
16" Maple S21°E 40.79'
8" Maple S49°W 50.12'
10" Red Pine N39°E 52.19'

* Old witness by others

J-3 Found 5/8" rered
Wit: * Power Pole N28°W 44.48'
4" Spruce N75°E 99.95'
6" Spruce S45°W 98.66'
* Power Pole Stub S39°W 55.23'
€ N-S Blacktop Road East 21.63'

* Old witness by others

Signed by: Carl T. Kiiskila
Surveyor's Michigan License No.: 33981

Date: 8-1-00

