

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
EMMET COUNTY
RECORDED

1994 FEB 14 AM 10:14

For corners in COMMISSION

EMMET (County)	Located In: FRIENDSHIP TOWNSHIP	Corner Code #: M-7
	36N 7W	
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Glenna A. Sipe

REGISTER OF DEEDS

LIBER A

PAGE 18

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard E. Oelke, in a field survey on 28 December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-7, Section corner 13, 18, 19, & 24, T36N, R7W
- 1840 GLO Set cedar post N81°W, 661ks, 4" balm & S59°E, 76 lks, 4" cherry
 - 1950 Schweighert Fd. iron pipe (1) N33°E, 61.2', 6" maple; (2) N51°W, 80.2', 10" maple.
 - 1965 Irish Survey for Swift, fd 1/2" iron pipe.
 - 1966 M. Feindt Unrecorded Plat of Wynhaven shows found iron.
 - 1971 B&Y Work drawing shows corner as witnessed in 1976 by REB.
 - 1971 Bidstrup Plat of Gaehaven, shows fd 3/8" iron pipe.
 - 1976 Bidstrup LCRG, Liber 1, page 213, fd. 3/8" iron pipe. (3) N35°E, 59.96', 8" maple (4) S55°E, 69.09', 14" maple (5) N34°W, 61.0', 6" aspen
 - 1987 Green Survey for Bank of Alma, shows 3/8" iron pipe as witnessed.
 - 1993 Oelke Plat of Cedar Bluff, as recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-7, Section corner 13, 18, 19, & 24, T36N, R7W
- Found 3/8" iron pipe, 3' long, .3' below the surface.
- N34°E, 59.92', fd (1)(3), 10" maple old nail in NW face
 - S58°E, 69.02', fd (4), 14" maple old nail in SW face
 - N51°W, 80.48', fd (2) 16" maple no nail or beep



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-7, Section corner 13, 18, 19, & 24, T36N, R7W
- At position of 3/8" iron pipe, set a 2" diam., 30" long, PVC pipe with a base magnet and a standard brass
- Emmet County Survey Remonumentation Program cap. 3' long, .3' below the surface.
- N34°E, 59.92', fd (1)(3), 10" maple old nail in NW face
 - N34°E, 59.63', 10" maple tagged #33983 in SE face
 - S58°E, 69.02', fd (4), 14" maple old nail in SW face
 - S53°E, 100.06', 14" w. birch tagged #33983 in SW face
 - S59°W, 99.95', 12" w. birch tagged #33983 in NW face
 - N52°W, 76.09', 12" oak tagged #33983 in NE face
 - N51°W, 80.48', fd (2) 16" maple no nail or beep

Signed by Richard E. Oelke Date 14 JANUARY 1994
 Surveyor's Michigan License No. 33983