

SURVEY &  
REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

96 DEC 31 PM 2:25

For corners in COMMISSION

EMMET  
(County)

Located In:

Corner Code #

- |                                    |                          |           |
|------------------------------------|--------------------------|-----------|
| 1. Public Land Survey              | T <u>37N</u> R <u>4W</u> | <u>E5</u> |
|                                    | T _____ R _____          | _____     |
| ECRP # 119                         | T _____ R _____          | _____     |
|                                    | T _____ R _____          | _____     |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____     |
|                                    | S _____ T _____ R _____  | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____     |
|                                    | S _____ T _____ R _____  | _____     |

*Allen B. Sizer*  
REGISTERED PROFESSIONAL SURVEYOR

LIBER A  
PAGE 119

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Trowbridge, in a field survey on December 16, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E5, CORNER COMMON TO SECTIONS 8, 9, 16, & 17, T37N, R4W

SEE BACK OF THIS FORM FOR HISTORY OF CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E5, CORNER COMMON TO SECTIONS 8, 9, 16, & 17, T37N, R4W

FOUND 2" PIPE @ LCRC @ L3, P133, & FOLLOWING WITNESSES:

- |             |      |        |   |
|-------------|------|--------|---|
| (3) AZIMUTH | 318° | 32.22' | Telephone pedestal post, cap #27463 & nail in east face |
| (4) AZIMUTH | 68°  | 56.23' | 8" Fir, cap #27463 & nail in north face                 |
| (5) AZIMUTH | 111° | 88.80' | 5" Birch, cap #27463 & nail in north face               |



APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County

P. E. OELWIG  
12.30.96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E5, CORNER COMMON TO SECTIONS 8, 9, 16, & 17, T37N, R4W

The 2" pipe above was removed, and replaced with a 2" diameter, 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program cap. This position is accepted as a careful and faithful perpetuation of the position of the original corner.

ADDITIONAL NEW WITNESSES:

- |         |      |        |  |
|---------|------|--------|--|
| AZIMUTH | 345° | 51.30' | Power pole, cap #27463 & nail in west face     |
| AZIMUTH | 241° | 71.12' | 9" Maple, cap #27463 & nail in northwest face. |

Signed by Michael A. Trowbridge

Date 12/20/1996

Surveyor's Michigan License No. 27463

EMMET COUNTY REMONUMENTATION PROGRAM

CHRONOLOGY OF GLO CORNER

LIBER A  
PAGE 120

REMON. CORNER # 119 LCRC # 37-04-E5 TOWNSHIP...MCKINLEY

CORNER COMMON TO SECTIONS 8,9,16,& 17 , T37N, R4W

DATE	SURVEYOR	FOUND/SET	WITNESSES
1840	GLO	SET POST	(1)BEECH 6 S24E 24 (2)BEECH 6 N13W 13
1894	MAIN	NOTES..."AND SETTING THE TEMPORARY CORNER OF SECTIONS 8,9,16 & 17, 42'4"E AND 26'8" S. ALSO SET POSTS 33' EAST & W. THIS IS A SINGLE PROPORTIONATE POSITION BETWEEN THE SE CORNER SECTION 17-37-4, AND THE EAST 1/4 CORNER SECTION 8-37-4. HE NOTES FINDING 3 STAKES IN RADIUS OF 30' @ E 1/4 COR. 17-37-4, & 5 STAKES IN RADIUS OF 150' @ NE CORNER 17-37-4.	
1909	SWIFT	NOTES... FROM NW CORNER 17-37-4 "S89°E 79.76 INTERSECT N&S LINE 62 FT. S. OF OLD POST WITH BEARINGS"	
1915	MAIN	NOTES... "COMMENCING AT A 2" GAS PIPE 3-1/2' SET AT THE CORNER OF SECS 8-9-16-17, 37-4".	
1994	TROWBRIDGE L3,P133	FOUND 2" PIPE & TOOK FOLLOWING WITNESSES:	(3)AZIMUTH 318° 32.22' TELE. PED. POST, 27463 CAP & NAIL (4)AZIMUTH 68° 56.23' 8" FIR, 27463 CAP & NAIL IN NORTH FACE. (5)AZIMUTH 111° 88.80' 5" BIRCH, 27463 CAP & NAIL IN NORTH FACE. (6)AZIMUTH 252° 62.05' 12" BASSWOOD, 27463 CAP & NAIL IN NORTH FACE.