

EMMET COUNTY REMONUMENTATION PROGRAM
CORNER NO. 116
T37N R4W - G-13

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

Date	Surveyor	Found	(Witnesses)	
1840	GLO	Set Post Corner	(1) (2)	Beech 6 - N38E 37 Beech 6 N77W 11
1892	S.G.Main	Set Large Cedar Post 8" Dia., 3-1/2' Long		
1893	S.G.Main	Set 7" Cedar Post, 4 feet long, 6" Below surface.		Set cedar posts @ angles of 45°, N45°E N45°W, S45°E, S45°W at outside Hwy. Limits.
1916	S.G.Main	T-Rail 5-1/2' Long at above 1892 Position		
1957	E.C.R.C.	Found survey stake	(3) (4) (5)	54.8' - S.E. Corner McRae Sidewalk S.E. 35.7' - Telephone Pole 55.7' - East Corner McRae Vault
1963	Schweigert & Young	Found 3/4" Iron Pipe		no witnesses
1969	R.E.Bidstrup	Corner noted as found		no witnesses
1969	J.H.Green	Corner noted as found		no witnesses
1969	G.E.Young	Found 3/4" Pipe		no witnesses
1972	G.E.Young	Found 3/4" Pipe		no witnesses
1973	J.H.Green	Found 1/2" Re-rod	(4) (3)	S.E. 35.7' - Telephone Pole 54.8' - S.E. Corner McRae Sidewalk
1979	R.E.Bidstrup	Found Iron Pipe	(3) (4) (5)	54.8' - S.E. Corner McRae Sidewalk S.E. 35.7' - Telephone Pole 55.7' - East Corner McRae Vault
1983	J.H.Green	Found Iron Pipe	(4) (3)	S.E. 35.7' - Telephone Pole 54.8' - S.E. Corner McRae Sidewalk
1984	J.B.O'Neill	Found 3/8" Pin in pvt.		no witnesses
1992	T.D.Swenor	Found 1/2" Re-rod	(4) (3)	S.E. 35.7' - Telephone Pole 54.8' - S.E. Corner McRae Sidewalk
1992	M.A.Trowbridge	Shows corner as found		No witnesses. Survey rec. L.475, P.172
1993	Fairrier	Found 1/4" Iron Pipe at T-Intersection	(6) (7) (8) (3) (9)	S57°W 37.58' - Power Pole N67°W 87.37' - Power Pole S40°W 55.22' - 7" Scotch Pine N50°W 55.00' - S.E. Corner McRae Sidewalk S75°E 131.91' - Power Pole
1995	R.E.Oelke	Found 1/4" Iron Pipe @ McRae St		