

98 DEC 31 AM 8:53

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in
Emmet
(County)

Located In:	Corner Code #
T <u>37N</u> R <u>5W</u>	<u>E-9</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Glenn B. Lipe
REGISTER OF DEEDS

LIBER A

PAGE 268

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Thomas D. Swenor, in a field survey on November 25, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-9 Section Corner common to Sections 20, 21, 28, and 29, T37N R5W

(SEE BACK OF PAGE FOR HISTORY)

1840 GLO established. 1912 Keep found cedar post said to have been kept from Gov't. Bearing, and recognized as correct NBT Elm 14, S88½°E 30' 5". 1960's ECRC found iron in place, and noted 30" Elm at S86°E 29.6". In 1975 Bidstrup notes 30" Elm at S86°E 30.8". Iron as found is on centerline of road north, south, and west. Iron as found is On fenceline east. History supports acceptance of corner at its present location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 Section Corner common to Sections 20, 21, 28, and 29, T37N R5W
Found 1/2" Re-rod above T-shaped forged farm implement (picture in file), in monument box as recorded in L.258, P.718, Certificate of Survey. Unable to verify Elm Stump/root wad, as there appears to have been earthwork in vicinity. Corner as found is on centerline of road north, south, and west. Iron as found is On fenceline east. Placed ECRP corner at top/center of T-shaped forged farm implement, and established new witnesses as noted below.

THIS CORNER IS ACCEPTED BY THE EMMET COUNTY REMONUMENTATION GROUP AS A FAITHFUL AND CAREFUL PERPETUATION OF THE ORIGINAL CORNER.

APPROVED LAND CORNER
P.A. 345 OF 1990
Emmet County
R.E. OELKE, P.S. EL-REP.
29 DEC 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 Section Corner common to Sections 20, 21, 28, and 29, T37N R5W
Found 1/2" Re-rod above T-shaped forged farm implement and replaced with a 2" diameter, 30" long PVC Pipe with a Base magnet and a standard Brass Emmet County Remonumentation Cap. Placed monument box to preserve corner.

- Witnesses:
- (6) S65°W 71.99' - Red Pine 10"
 - (7) S42°E 58.27' - Scotch Pine 10"
 - (8) S83°E 58.07' - Fence Post Corner
 - (9) N57°E 54.34' - Red Pine 6"



Signed by Thomas D. Swenor Date 12-29-98
Surveyor's Michigan License No. 37282

MASSACHUSETTS
 1780
 1790
 1800
 1810
 1820
 1830
 1840
 1850
 1860
 1870
 1880
 1890
 1900
 1910
 1920
 1930
 1940
 1950
 1960
 1970
 1980
 1990
 2000

EMMET COUNTY REMONUMENTATION PROGRAM
 CORNER NO. 182
 T37N R5W E-9

LIDET A
 PAGE 269

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION

Date	Surveyor	Found	(Witnesses)
1840	GLO	Set Section Post	(1) Beech 10 S55°E 09 (2) Birch 18 N33°W 17
1912	John Keep	Cedar Post	(3) S88-1/2 E 30' 5" - NBT Elm 14
1962	DNR	Found Iron in place set 1/2" Bar on top to surface.	
1960's	ECRC	Left Iron in place, set 1/2" rod on top to surface	(3) S86E 29.6' - Elm 30 (4) N31E 99.20' - Apple 6
1975	R. Bidstrup	Found 5/8" Re-rod in monument box	(5) S15W 111.9' - Power Pole (3) S86E 30.8' - Elm 30
1980's	J.H. Green	Map and distance along south line of Sec 20 is 2640.66'	
1995	T. Swenor	Found 5/8" Re-rod in monument box.	