

**SURVEY & REMONUMENTATION**

MAR 04 1998

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

97 DEC 29 PM 3:09

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

*Glenna B. Sipes*  
REGISTER OF DEEDS

EMMET  
(County)

Located In: Corner Code #

- |                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>37N</u> R <u>5W</u> | <u>K-11</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |

**LIBER A PAGE 172**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas D. Swenor, in a field survey on December 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-11, Section Corner common to Sections 25, 26, 35, and 36, T37N R5W

Date	Surveyor	Found	Witnesses
1840	GLO	Set Sec. Post	(1) Cedar 8 S21W 06 (2) unknown 6 S18E 15
1962	G.E. Young	Dept. of Cons. Map	doesn't show found corner
1982	K.J. Ostling (DNR)	Set D.N.R. Monu. (L.2, P.151, LCRC)	(3) S45°W 20.30' - 4" R. Maple (4) S18°E 22.40' - 7" W. Birch

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-11,  
Found DNR Monument, (1" Pipe with 4" cap) as set by K.J. Ostling (See Liber 2, Page 151, LCRC). Found and verified both Ostling witnesses. Old fence line, mostly lying down, extends south from Pipe. Pipe fits centerline of Pleasantview Road (north), and Camp Road (east). Camp road appears to have extended though this location, as an old grade area is evident at this location.


THE DNR MONUMENT REPRESENTS THE BEST AVAILABLE EVIDENCE FOR THIS CORNER.

APPROVED LAND CORNER.  
P.A. 345 OF 1990  
Emmet County  
*P.E. DELVE*  
E.C.R.P. Rep.  
12-30-97

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-11,  
Found DNR Monument, (1" Pipe with 4" cap) as set by K.J. Ostling (See Liber 2, Page 151, LCRC) and replaced with a 2" diameter, 30" long PVC Pipe with abase magnet and a standard brass Emmet County Remonumentation Cap.

- Witnesses:
- (3) S43°W 20.46' - 6" R. Maple (found DNR witness)
  - (4) S21°30'E 22.52' - 12" W. Birch (found DNR witness)
  - (5) N01°W 44.50- 8" Scotch Pine (set spike nail with 37282 cap)
  - (6) N69°E 86.19' - 8" Maple (set spike nail with 37282 cap)



Signed by Thomas D. Swenor Date 12/29/97  
Surveyor's Michigan License No. 37282