

**SURVEY & REMONUMENTATION**

**MAR 04 1998**

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

97 DEC 29 PM 3:09

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

EMMET  
(County)

Located In:

Corner Code #

- |                                    |   |            |            |             |
|------------------------------------|---|------------|------------|-------------|
| 1. Public Land Survey              | T | <u>37N</u> | <u>R5W</u> | <u>L-11</u> |
|                                    | T | _____      | R_____     | _____       |
|                                    | T | _____      | R_____     | _____       |
|                                    | T | _____      | R_____     | _____       |
| 2. Property Controlling in Section | S | _____      | T_____     | R_____      |
|                                    | S | _____      | T_____     | R_____      |
| 3. Miscellaneous Property in Sec.  | S | _____      | T_____     | R_____      |
|                                    | S | _____      | T_____     | R_____      |

ECRP #138

*Glenns L. Sizer*  
REGISTER OF DEEDS

**LIBER A PAGE 171**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas D. Swenor, in a field survey on 12/19, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-11, Quarter (1/4) Corner common to Sections 25 and 36, T37N R5W			
<u>Date</u>	<u>Surveyor</u>	<u>Found</u>	<u>Witnesses</u>
1840	GLO	Sugar 15, 1/4 post	Tree is corner
1982	K.J. Ostling (DNR)	Set P.K. Nail	South 1/4 Corner was set in line with fence north, on line between section corners

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


L-11,  
Found P.K. Nail as set by K.J. Ostling. P.K. Nail is in the centerline of Camp Road (east/west) P.K. Nail is also on the extension of a very old fence line north. The fence line is all standing, and maintained by adjacent owners. P.K. Nail is six foot east of a newer fence line south. Dug four foot below found P.K. Nail and found nothing.

THE P.K. NAIL REPRESENTS THE BEST AVAILABLE EVIDENCE FOR THIS CORNER.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County  
P.E. OELKE  
ECRP REP  
12-30-97

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-11,  
Found P.K. Nail as set by K.J. Ostling and replaced with a 2" diameter, 30" long PVC Pipe with abase magnet and a standard brass Emmet County Remonumentation Cap.  
Witnesses:  
(1) N17°W 57.04' - Maple clump (set spike nail with 37282 cap)  
(2) N03°30'E 58.68' - 12" Maple (set spike nail with 37282 cap)  
(5) N47°E 82.98' - 10" Maple (set spike nail with 37282 cap)  
(6) S14°E 54.43' - 18" Red Pine (set spike nail with 37282 cap)



Signed by Thomas D. Swenor Date 12/29/97  
Surveyor's Michigan License No. 37282