

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N. R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22 - 23 - 26 - 27

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 18, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

12" Spruce N 38 W 55.4'

6" Cherry N 62 E 18.1'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a retracement in this area. Set corner by proportionate measurement between section corners 1 mile east, 1 mile west, 1 mile north, and 2 miles south. No evidence of a previous corner or U. S. BTs. This point conforms exactly with the position prescribed by a line over an old fence corner considered acceptable as the S 1/4 corner of Section 23 and the existing SE corner of Section 23, also making the 1/2 miles of equal measurement.

SURVEYOR'S SEAL

SIGNED Kenneth Osting DATE June 20, 1962
REGISTERED LAND SURVEYOR