

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N. R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14 - 15 - 22 - 23

CORNER MONUMENT Set 1" pipe with 4" brass cap below surface

DATE MONUMENT PLACED AND WITNESSED June 18, 1962

WITNESSES TO CORNER.....



6" Aspen N 14 W 59.6'

Power Pole S 53 W 58.3'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was restored while making a survey in this area. Set corner by proportionate measurement for longitude between Section corner 1 mile east and 1/4 corner 1/2 mile west, and on line over 1/4 and section corner west for latitude. This falls in line with center of old township road south and conforms very well with centerline of E - W County Road. Unable to locate anything for a previous corner.

**SURVEYOR'S SEAL**

SIGNED *Kenneth J. Oetken* DATE June 20, 1962  
REGISTERED LAND SURVEYOR