

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N.R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 21 - 28

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 13, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" Tamarack N 68 E 43.6'

6" W. Birch S 21 E 46.4'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was set while making a survey in this area. Set corner at fence corner, which we conclude to mark the position established in the survey of Section 28 by County Surveyor S. Main in 1912. Found glass bottle buried at corner also. This point checks measurement on north line of Section 28, and conforms to measurement of east line of Section 28 for latitude. Best available evidence.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling  
REGISTERED LAND SURVEYOR

DATE

June 14, 1962