

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N.R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28 - 29 - 32 - 33

CORNER MONUMENT Set 1" pipe with 4" brass cap below surface

DATE MONUMENT PLACED AND WITNESSED June 13, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" Elm N 82 E 33.1'

30" Maple N 8 E 80.4'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was establish while making a survey in this area. Any previous corners removed in road construction. Set this corner on line over 1/4 and section corner north, at proportionate measurement between 1/4 corners north and south for latitude.. This falls near centerline of County Road, and conforms for measurement to a survey of record by S. Main in 1912. Checks measurement east also. It is felt this is a very close restoration of the corner as identified by Main, and is acceptable as the proper position for corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE June 14, 1962  
REGISTERED LAND SURVEYOR