

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N. R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 27 - 28

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 12, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" B. Cherry S 83 E 39.1'

10" B. Cherry S 15 W 37.1'

AND

36" W. Pine stump N 53 E 68.0'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this area. Found a 5/8" iron rod for 1/4 corner as established by County Surveyor Sidney Main in 1912. No evidence of U. S. BTs. Conforms exactly to measurements of record returned in 1912 survey.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Wetling
REGISTERED LAND SURVEYOR

DATE

June 14, 1962