

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 27 - 28 - 33 - 34

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 12, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

20" W. Pine stump S 40 E 37.1'

6" Balsam S 57 W 25.3'

AND

8" W. Birch N 48 E 15.0'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a retracement of this area. Found a 7/8" iron bar (axle) at corner as found and accepted in a survey of Section 28 by Sidney Main, County Surveyor in 1912. Accepted by Main as having been restored from probable U. S. BTs in an earlier survey. Considered acceptable as an old corner of long standing, probably a restoration of original corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE June 14, 1962
REGISTERED LAND SURVEYOR