

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N. R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 20 - 21 - 28 - 29

CORNER MONUMENT Left iron in place. Set 1/2" rod on top to surface.

DATE MONUMENT PLACED AND WITNESSED June 12, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

30" Elm S 86 E 29.6'

6" Apple tree N 31 E 99.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this area. Found piece of iron surrounded by rocks 1 foot below surface of road intersection, in line with fence east. This corner previously restored by County Surveyor Sidney Main in 1912. His Elm NBT still in place, now 30" and used as our NBT. Good corner of long standing.

SURVEYOR'S SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE

June 12, 1962