

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N. R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side section 33

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 19, 1962

WITNESSES TO CORNER.....



AND

8" Balsam N 48 E 28.1'

7" Cedar N 65 W 48.2'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corners while making a survey in this township. Can locate nothing for previous corner. Falls about 12' north of apparent centerline of E - W county road.

1/4 corner for Section 4, T 36 N, R 5 W is 4 links west.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Bething* DATE June 21, 1962
REGISTERED LAND SURVEYOR