

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 5 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28 - 33

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 18, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

12" Elm N 11 W 23.4'

8" Maple S 71 W 56.9'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this area. Set corner at very old fence intersection north - south - west which appears to have been constructed in accordance with a survey by S. Main, County Surveyor, in 1912. This position checks closely with the record of the 1912 survey and is considered the best available evidence of the proper position for the corner. Falls exactly on line between existing section corners east and west.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE June 21, 1962
REGISTERED LAND SURVEYOR