

**SURVEY & REMONUMENTATION**

MAR 13 2000

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

99 DEC 28 AM 9:36

For corners in

EMMET  
(County)

Located In: READMOND TOWNSHIP  
Corner Code #

*Glenn A. Sizer*  
REGISTER OF DEEDS

1. Public Land Survey T 37N R 6W G-3  
ECRP #199

2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LICER A  
PAGE 312

Register of Deeds Stamp & File Number

I, Richard E. Oelke, in a field survey on 10 December, 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3							●						
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**Abstract:** GLO set corner in 1840's. In 1992, Swenor set pk, O'Neill found pk and replaced with 5/8" rod, at centerline of State Rd., 3' S. of Division Rd. It has been used in subsequent surveys by local surveyors.

See back page for chronological history of corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Found:** at the intersection of Division and State Roads, approximately 3' below surface, the rotted remains of an old post, alongside a 1'x8"x1.5' granite rock, above old glass, metal, leather and another large stone. The 5/8" iron rod, in centerline of State Rd., 3' S. of centerline of Division Rd. was removed

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County  
R.E. OELKE  
ECRP REP. 12-23-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Set:** The granite rock noted above was removed, and replaced with a 2" diameter, 30" long, PVC pipe with a base magnet and a standard brass Emmet County Survey Remonumentation Program Cap, which was placed within a standard monument box. This position is accepted as a careful and faithful perpetuation of the position of the original corner.

Additional New Witnesses:

- 1) N 67°E, 79.31', pp, tagged 33983, in SE face
- 2) S 75°E, 130.66', pp, tagged, 30095, in S face
- 3) S 39° W, 89.53', 8" pine, nail SE face, added new nail tagged 33983
- 4) N 81°W, 222.82', pp, tagged 30095, in the S face



Signed by R.E. Oelke  
Surveyor's Michigan License No. 33983

Date 10 December 1999

SURVEY &  
REMONUMENTATION

MAR 13 2000

L.I. 571 A  
PAGE 313

SECTION

EMMET COUNTY REMONUMENTATION PROGRAM  
CORNER NO. 199

37-6-G3

T37N R6W section corner bet. Secs. 3,4,9, 7 10  
DIVISION and STATE ROADS

Date	Surveyor	Found	Witnesses	Notes
1840	GLO	Set post	1) N 86°E 14L 8" Beech 2) N 68°W 12L 9" Beech	
1992	Swenor	set pk nail using ROW fences to the SE		
1992	O'Neill	survey for Ira, fd. Large PK nail, replaced with a 5/8" rerod, 3' S of Intersection	1) N 64°E, 79.86', tag 30095 in power pole 2) S 76°E, 129.76', tag 30095 in power pole 3) S 40°W, 86.25', tag 30095 in 4" pine 4) N 80°W, 223.43', tag 30095 in power pole	
1992	Swenor	fd. 5/8" rebar		
1997	Young	fd. 5/8" rebar		