

APR 29 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
EMMET COUNTY  
RECORDED

1995 DEC 19 PM 1:37

*Glenna L. Sizer*  
REGISTER OF DEEDS

For corners in EMMET Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

- 1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
EMMET COUNTY REMON. CORNER #97 T \_\_\_\_\_ R \_\_\_\_\_  
COMMON TO SECTIONS 2 & 3 T 37 N R 6 W 11  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

LIBER A  
PAGE 87

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael A. Trowbridge, in a field survey on DECEMBER 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
11...CORNER COMMON TO SECTIONS 2 & 3, T37N, R6W

SEE EMMET COUNTY REMONUMENTATION PROGRAM CHRONOLOGY OF GLO CORNER ON BACK SIDE OF THIS PAGE.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Emmet County  
*R.E. Oves*  
21 Dec. 95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
11...FOUND 1/2" REROD WITH CAP 27463. THIS WAS SET AT STANDARD OFFSET AND ON LINE BETWEEN THE SOUTHWEST AND SOUTHEAST CORNERS OF SECTION 35, T38N, R6W AS NOTED IN 1990 TROWBRIDGE LAND CORNER RECORDATION CERTIFICATE, LIBER 2, PAGE 317.

FOUND WITNESSES

- 3) WEST 31.02' 5/8" REROD WITH CAP 11360
- 4) AZIMUTH 17° 47.94' POWER POLE (SPIKE IN WEST FACE)
- 5) AZIMUTH 82° 27.98' 10" MAPLE (SPIKE IN NORTH FACE)
- 6) AZIMUTH 116° 34.42' 8" MAPLE (SPIKE IN NORTH FACE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11...THE 1/2" REROD WAS REMOVED AND REPLACED WITH A 2" DIAMETER X 30" LONG PVC PIPE, A BASE MAGNET AND A STANDARD BRASS EMMET COUNTY REMONUMENTATION CAP. THIS POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

- 3) WEST 31.02' EMMET COUNTY REMONUMENTATION MONUMENT
- 4) AZIMUTH 17° 47.94' POWER POLE (SET 27463 CAP AND NAIL IN WEST FACE)
- 5) AZIMUTH 82° 27.98' 10" MAPLE (SET 27463 CAP AND NAIL IN NORTH FACE)
- 6) AZIMUTH 116° 34.42' 8" MAPLE (SET 27463 CAP AND NAIL IN NORTH FACE)



Signed by Michael A. Trowbridge  
Surveyor's Michigan License No. 27463

Date 12/11/95

