

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N. R. 6 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side Section 32

CORNER MONUMENT 1" pipe with 4" brass cap below surface

DATE MONUMENT PLACED AND WITNESSED June 25, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

12" Twin Elm N 35 E 48.0'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was found while making a survey in this area. Found a 4" x 4" piece of strap iron (sleigh runner), also part of old coal shovel and a railroad spike at corner which we conclude to be 1/4 corner for Section 32 since it falls midpoint between section corners and only 5 links out of line.

Falls on west edge of 1/4 line road south, but is considered the result of early local survey and appears acceptable.

1/4 for Section 5, T 36 N, R 5 W is 10 links west.

**SURVEYOR'S SEAL**

SIGNED

Kenneth J. Ostling  
REGISTERED LAND SURVEYOR

DATE June 27, 1962