



SECTION

EMMET COUNTY REMONUMENTATION PROGRAM  
CORNER NO. 173A

LINEN A  
PAGE 281

38-4-A3  
T38N R5W CORNER COMMON TO SECTIONS 1/6/7/12  
INT. ELDER & PHILLIPS ROAD

Date	Surveyor	Found	Witnesses
1840	GLO	Set post	A) S45E 15L 40" Cedar B) N80W 12L 12" Cedar
1922	Saxton	found 6" cedar post, replaced with concrete post	1) S20E 23.3' rock 2) S45W 36.0' fence corner 4) N45W 37.0' fence corner
1980	Ferguson	LCRC (L2 P14) found 1/2 iron rod in CL Elder rd no evidence found of prior witnesses	5) N53E 65.0' 6" Cherry 6) S35E 52.1' boulder w/ cap in pore 7) S75W 38.5' utility pole 8) N10W 35.0' utility pole
1984	Roser	found 5/8 bent rod and note with what Saxton found	
1993	Roser	LCRC (L3 P95) found 5/8 rod over 4*4 sq conc monument	9) N55E 55.74' 4*4 treated post w/ metal teleph riser 10) S35W 39.35' PP 11) N40W 36.07' guy pole