

Remon # 208
 T38N R4W Carp Lake Township
 G-13SC: Section 33,34
 Levering Road and Reed Road

LIPER A
 PAGE 360

| | | | |
|---------------------------------|--|---|---|
| 1840's | GLO PG. 116,117, PG. 146,147 | West on South Side 80.00 Sec. 34; Set Post Corner Sec. | (1) Cedar 7 N74E 18 (2) Birch 8 N40W 22 |
| 1840's | GLO PG. 132,133 | North Between Sec. 3 & 4 T37N R4W: 79.75 Intersect N. Boundary 20 West of Post Set Post Corner Sec. 3 & 4 | (3) Beech 15 S18E 29 (4) Sugar 10 S9W 40 |
| 1882 Note: Plat Shows Corner | O. S. Henden | Map of Levering | |
| 1893 | S. G. Main PG. 302-303 | Set Cedar 7 in 3 ft long below surface also Cedar 6 in 3 ft long 2 feet in ground 50L E and 50L W Some of Gov. Bearings found but Burned down. Set this post by Posts Found of the survey of the Village of Levering - Which was made before it was burned when bearings were standing. | |
| 1914 | S. G. Main PG. 264-265 | Cor. Sec. 3-4 N Boundary. One Bearing Tree Stands for N. Town Set Cedar Post 20L W | |
| Circa 1960's | Emmet County Road Commission 414 #23 | Sec Cor. Common to Sec. 33 & 34 T38N R4W. P.K. Nail Cor. to Sec. 3 & 4 T37N R4W is 13.20' W | No Wit's |
| 1970's | J. H. Green | Map showing 13.20' Separation Between Corners distance to East 1/2" rod | (5) N45°W 36.70' Conc. Hwy (6) S50°W 36.22' Conc. Hwy (7) S55°E 57.27' Power Pole (8) North 43.98' Road Sign |
| 1975 | J. H. Green | SW Cor. Sec 34, T38N R4W | (9) S45°E 46.26' Power Pole (10) N16°W 51.59' Power Pole |
| 1989 | M. A. Trowbridge L. 2 Pg. 302 | G-13 Sec. 34, T38N R4W Found P.K. Nail | (10) Az. 344° 51.37' P.P. (9) Az. 130° 46.24' P.P. (11) West 13.23' 5/8" rod (12) S89°49'41"E 1318.12' 1" pipe in mon box |
| 1989 | J. B. O'Neill | Found P.K. Nail Set 5/8" Re-rod | (10) S 45° E 46.26' Power Pole (9) N16°W 51.59' Power Pole (13) S64°W 70.44' 4" x 4" Post (14) N76°W 98.93' Guard Post |
| 1994 | R. E. Oelke | Found 5/8" Re-rod | (10) S 45° E 46.26' Power Pole (9) N16°W 51.59' Power Pole (13) S64°W 70.44' 4" x 4" Post (14) N76°W 98.93' Guard Post |
| 1998 | T. D. Swenor | Found 5/8" Re-rod | Fenceline ties to the west verify this corner position. |

SURVEY &
 REMONUMENTATION

MAR 13 2000

SECTION