

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 4 W.
T. 39 N.R. 4 W.


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 - 34

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 22, 1962

WITNESSES TO CORNER.....



10" W. Birch S 47 E 22.3'

5" Maple S 34 W 52.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line between section corners. No sign of previous corner but this point falls in line with old fence line north and about five feet south of centerline of old E - W township grade.

SURVEYOR'S SEAL

SIGNED Kenneth J. Osting DATE May 28, 1962
REGISTERED LAND SURVEYOR