

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 38 N.R. 4 W.  
T. 39 N.R. 4 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3 - 4 - 33 - 34

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 21, 1962

WITNESSES TO CORNER.....



7" Balsam S 10 W 36.2'

7" Balsam N 87 E 83.8'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was established by single proportionate measurement between section corners one mile east and two miles west while making a survey in this area. Unable to locate anything for a previous corner. Falls about 140 feet east of N - S trail on old RR grade. Checks 1/4 line fence east.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Downing* DATE May 28, 1962  
REGISTERED LAND SURVEYOR