

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 4 W.
T. 39 N.R. 4 W.


Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4 - 5 - 32 - 33

CORNER MONUMENT Set 1" pipe with 4" brass cap below surface

DATE MONUMENT PLACED AND WITNESSED May 22, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" Spruce S 8 W 60.2'

5" Dead Balsam N 54 W 58.9'

AND

5" Balsam N 38 W 66.0'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between Section corners one mile west and two miles east while making a survey in this area. No sign of a previous corner, but this point falls in centerline of E - W township grade and approximately in line with old trail south.

SURVEYOR'S SEAL

SIGNED Kenneth J. Oetting DATE May 22, 1962
REGISTERED LAND SURVEYOR