

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 FEB 14 AM 10:12

For corners in
EMMET COMMISSION
(County)

Located In: Corner Code #

- 1. Public Land Survey T 38N R 5W G-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Elenna L. Sizer

REGISTER OF DEEDS

Liber A

PAGE 2

Register of Deeds Stamp & File Number

I, Thomas D. Swenor in a field survey on December 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-3

- 1840 G.L.O. John Mullett Set Post Corner Section 3,4,9,10 Hemlock 12" N45E 26 links, Beech 9" N19W 08 links.
- 1902 M. Palmer (County Surveyor) Found Government Corner and set 6" Cedar Post. (as stated on Pg. 18 of Large County Surveyors Liber at Emmet County Register of Deeds).
- 1985 Roser (DNR) - R. O'Hara, John Swanson, Harold Kibbe found Cedar Post Bottom, vertical, (6" Rotted) while scalping for cor. from survey data from retracement of M. Palmer's 1902 survey of Sec 9, Oct 9, 1985. O'Hara showed this corner to

* Section "A" Continued Below

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C. Roser on Oct 15, 1985 who verified this as recovering M. Palmer's Cedar Post, Palmer having the Orig 1840 G.L.O. Cor. Roser Took Photographs of the recovered cedar post bottom in place. Roser leaned post bottom West and drove 5/8" X 35" Re-Rod with Plastic RLS Cap # 12028. See Liber 2, Page 142, Emmet County Register of Deeds.

* Begin Section "B"

G-3

- Found as described and recorded in 1985 by Carl Roser (DNR). Witnesses Fit well, and the history of the corner appears to be consistent with this position.
- This corner is accepted by the Emmet County Remonumentation Peer Group as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3

- Found 5/8" X 35" Re-rod with plastic RLS Cap #12028 and replaced with a 2" diam. 30" Long PVC Pipe with a base magnet and a standard brass Emmet County Remonumentation cap.
- Found Cedar Post W/Loc Tag West 33'
- Found spike W/Rusty cap 17" Red Oak S83W 50.50' (50.51 Roser)
- Found spike W/Rusty cap Old Cor Fn Post (irreg fn remains S'ly & W'ly) N25W 103.68' (103.64 Roser)
- Found spike W/Rusty cap 15" Red Oak S51E 58.14'
- Found 3/4" Rod N05°50'E 93.77' (93.78' Roser)
- Ctr N-S Gravel Rd (Looking South) East 3'+/-
- Ctr Graver Rd In Curve East 16'+/-

Signed by Thomas D. Swenor Date December 30, 1993

Surveyor's Michigan License No. 37282

