

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 5 W
T. 38 N R 6 W


Emmet COUNTY

DESCRIPTION OF CORNER Meander Corner common to Sections 25-30 on south side

CORNER MONUMENT 1" pipe with 4" brass cap Wycamp Lake

DATE MONUMENT PLACED AND WITNESSED April 27, 1961

WITNESSES TO CORNER.....



6" Balsam - S2W - 19 $\frac{1}{4}$ links

9" W. Birch - N45E - 40 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established on the calculated true line between the section corner south and the original meander corner on north side of Wycamp lake. Set corner about 60 links south of waters edge to preserve from water action when lake is up. Unable to identify Aspen corner tree.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 5/24/61
REGISTERED LAND SURVEYOR