

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 38 N.R. 5 W
T38 NR 6 W
Emmet COUNTY

DESCRIPTION OF CORNER Meander Corner common to Sections 13-18 on Lake Michigan

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 27, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

10" W. Pine	-	N74E	-	165½ links
6" R. Oak	-	S84W	-	103½ links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored on line over original Section and 1/4 corners south, at record government measurement. Unable to identify government BTs, but this point falls at a reasonably acceptable position. Set 1" pipe on beach ice roll at 272½ links north of meander corner, and on projected true town line.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 5/24/61
REGISTERED LAND SURVEYOR