

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 38 N. R. 5W
T. 38 NR 6 W Emmet COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 30, 31, 25, and 36

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 27, 1961

WITNESSES TO CORNER..... 4" Cedar - S50W - 7 links



5" Spruce - N46W - 27 links

5" Cedar - N16E - 14 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between town corner south and meander corner north side Wycamp Lake. Unable to identify government BTs, but this point checks swamp edge south and west, and fits lake shore north.

SURVEYOR'S SEAL

SIGNED Kenneth J. Oething DATE May 24, 1961
REGISTERED LAND SURVEYOR