

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 5 W
T. 38 NR 6 W


Emmet COUNTY

DESCRIPTION OF CORNER Witness Corner to the meander corner between Sections
25-30 on north side Wycamp Lake

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 6, 1961

WITNESSES TO CORNER.....



12" R. Pine - N4E - 198½ links

14" R. Pine - S83W - 249 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Restored position for original Meander corner which falls in lake from government BT stumps, both in place, exact. Found a little evidence of face on rotted NW stump, and collected pieces of ingrowth for file. Set Witness corner to this Meander corner 13 links north of meander corner to preserve from water action. Meander corner checks very well for line over good corners north, but definitely shows a five chain government error in the 1/4 mile north.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 5/24/61
REGISTERED LAND SURVEYOR