

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 5W


Emmet COUNTY

DESCRIPTION OF CORNER 1/4 Corner common to Sections 28 and 33.

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 19, 1961

WITNESSES TO CORNER.....



12" H. Maple - S62W - 93 1/2 links

10" H. Maple - N21W - 55 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was fixed at a well defined 1/4 line fence running north through Section 28 and south into Section 33, which also places it at midpoint on line between section corners. Government BTs all gone. Appears to be best available evidence of proper location for corner.

SURVEYOR'S SEAL

SIGNED Kenneth J. Oetting DATE May 24, 1961
REGISTERED LAND SURVEYOR